

Exhibit VIII.C.20.e – Proposed Opening Date of Gaming Facility

Submit as Exhibit VIII.C.20.e. a proposed date for the proposed Gaming Facility to open for gaming and indicate major risks to such proposed opening date and the range of probable delays associated with each. Describe plans to mitigate such risks. Indicate whether the proposed Gaming Facility will open in phases or all at one time. If the facility is to open in phases, provide a detailed description of what will open in each phase and the proposed opening date for each phase and/or what conditions each such opening date will be contingent upon. Provide Applicant's commitment for a proposed outside date, notwithstanding any delays, for substantial completion of the initial fully operational phase of the proposed Gaming Facility.

The proposed date for the completion of the new casino facility is June 20, 2016. After evaluating the proposed facility for the Capital View Casino & Resort, we believe one minor construction risk may be weather.

LPCiminelli is a Buffalo-based firm and has delivered \$400 million annually—invariably through Buffalo's stereotypical harsh winter conditions. Whether pouring concrete, roofing or installing façade materials, LPCiminelli has the experience and experienced staff to creatively ensure the project stays on schedule and meets quality standards.

Examples of extra measures taken for winter conditions are as follows:

- Fully heated concrete, concrete accelerators, other concrete additives to allow concrete pours to take place
- Enclosing the building for concrete pours and for spray fire proofing operations inside
- Scaffolding, tenting and heating for exterior brick/masonry and exterior spray insulation work
- Use of special fire rated, yet weather resistant products, in lieu of spray fire proofing (which are moisture and temperature sensitive) where necessary
- Temporary roofing
- Temporary heaters and temporary gas piping to ensure heat reaches all areas needing it
- Glycol blanket system for frost removal
- Moveable, panelized enclosures to expedite follow on trades

